

NOTICE OF EXEMPTION

By Deputy: kmchugh



TO:  Office of Planning and Research  
CEQAnet Web Portal  
<https://ceqasubmit.opr.ca.gov/>

FROM: San Joaquin County  
Department of Public Works  
1810 East Hazelton Avenue  
Stockton, California 95205

County Clerk  
County of San Joaquin California  
44 North San Joaquin Street, Suite 260  
Stockton, California 95202

Project Title: Eight Mile Road Resurfacing

Project Location: See attached vicinity map

Description of Nature, Purpose, and Beneficiaries: See attached project description

Public Agency Approving Project: San Joaquin County Public Works Department

Name of Agency Carrying Out Project: San Joaquin County Public Works Department

This is to advise that the San Joaquin County Public Works Department has approved the above described project on 6/18/2024 and has made the determination that the project is exempt due to the following:

Exempt Status (check one):

- Ministerial (Sec. 21080 (b) (1); 15268)
- Declared Emergency (Sec. 21080 (b) (3); 15269(a))
- Emergency Project (Sec. 21080 (B) (4); 15269(b) (c))
- Categorical Exemption: Existing Facilities (Sec. 15301 (c))
- Statutory Exemption (Sec. 15282(l))

Reason(s) why project is exempt: The project will repair an existing road and will not result in any major alterations to the configuration of the road. No additional vehicle travel lanes will be constructed.

Lead Agency Contact Person: Marilissa Loera, Senior Planner, (209) 468-3085

Signature:  Title: Senior Planner Date: 4/2/2025

# EIGHT MILE ROAD RESURFACING

## Project Description

### **Project Location:**

North 99 Frontage Road to Jack Tone Road. **See attached Vicinity Map.**

### **Project Justification:**

Eight Mile Road was constructed in 1961-62 (0.21 feet of asphalt concrete/0.50 feet of aggregate base/0.50 feet of aggregate subbase) and resurfaced in 1982 (0.15 feet of asphalt concrete) and 1996 (0.17 feet of asphalt concrete). The existing roadway has been periodically chip sealed and the most recent maintenance for a chip and crack seal in 2016-17.

Eight Mile Road from North 99 Frontage Road to Jack Tone Road, has moderate cracking visible along the road. The drive along Eight Mile Road is not smooth. Reports of flooding just west of State Route of 88. This road has a high volume of vehicle & truck traffic, and Overall Condition Index section rates as low as 50.

### **Scope of Work:**

The project will consist of:

1. Resurfacing existing roadway (32-48 feet wide) with 0.17 feet of Hot Mix Asphalt (HMA) (Type A).
2. Repairing Pavement structural failure areas with full depth 0.5 feet of HMA (Type A).
3. Replenishing 4-foot-wide Shoulder Backing: 2 feet (8%) and 2 feet to conform.
4. Constructing HMA (Type A) driveways.
5. Cleaning drainage ditches/culverts.


### **Environmental Setting:**

In these portions of the San Joaquin County, land usage is primarily **rural with single family homes.**

**There are many large trees adjacent to the project area.** Nesting and migratory birds, protected by the Migratory Bird Treaty Act, may nest within these trees. Furthermore, the Swainson's Hawk, a raptor species of concern within the State of California and listed as threatened may nest adjacent to or within the project area. A pre-construction survey for nesting Swainson's Hawks and other migratory birds is recommended if construction is scheduled to occur from February 15<sup>th</sup> to September 1<sup>st</sup>.


### **Beneficiaries:**

The public will see increased safety and fewer hazards with this well-maintained road. Overall, there will be reduced maintenance concerns and more reliability within the project area.



D4

NO SCALE



**Vicinity Map**  
**EIGHT MILE**  
**ROAD RESURFACING**

( N 99 Frontage Road to Jack Tone Road )

